

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford

County, Sec. 6 Twp. 25S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SW SW

Lease Owner Tomlinson-Kathol, Inc. & Shawver-Armour, Inc.

Lease Name Mather Well No. 1

Office Address 407 Board of Trade Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) O & A

Date well completed 7/10 1962

Application for plugging filed 7/10 1962

Application for plugging approved 7/10 1962


Plugging commenced 7/10 1962

Plugging completed 7/10/ 19 62

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Herman Justice

Producing formation None Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8-5/8"	266'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud was put into the hole to a depth of 200 feet where the bottom plug was set and cemented with 20 sacks cement. Mud was again put into the hole to a depth of 20 feet where the top plug was set and cemented with 10 sacks cement. Casing was cut off below ground level and the location abandoned.

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1962

CONSERVATION DIVISION
Wichita, Kansas

7-19-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol, Inc.

Address 407 Board of Trade Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Warren E. Tomlinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren E. Tomlinson
407 Board of Trade Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 1962

Evelyn Lane
Notary Public.

My commission expires 1/19/65



15-185-01361-0000

DRILLERS LOG
TOMLINSON-KATHOL, INC.
& SHAWVER-ARMOUR, INC.
1 MATHER
SE SW SW, SEC. 6-25S-12W
STAFFORD COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Commenced: 6/28/62
Completed: 7/10/62
Elevation: 1914 KB

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	80	Sand	
80	266	Red Bed	269' 8-5/8" w/210 sacks cement
266	545	Shale	
545	1025	Lime, Shale	
1025	1760	Shale	
1760	1870	Lime & Shale	
1870	1950	Lime	
1950	2675	Lime & Shale	
2675	2900	Shale & Lime	
2900	3045	Lime & Shale	
3045	3105	Shale & Lime	
3105	3430	Lime & Shale	Heebner 3405
3430	3641	Shale & Lime	Brown Lime 3552
3641	3670	Lime & Shale	Lansing 3582
3670	3850	Lime	
3850		Total Depth	

I certify to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

Warren E. Tomlinson
Warren E. Tomlinson

STATE OF KANSAS)
)
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 17th day of July, 1962.

Esther Lamone
Esther Lamone, Notary Public

My Commission Expires: Jan. 19, 1965