

Give All Information Completely
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Strike out upper line when reporting plugging off formations.

NORTH

**Locate well correctly on above
Section Plat:**

Name of Conservation Agent who supervised plugging of this well.

Producing formation NO PRODUCTION Depth to top _____ Bottom _____ Total Depth of Well 4208 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Hole was filled with concrete and the
with a 1" pipe. Surface pipe was
filled with mud & a bent pipe ran
from the surface to the bottom of well (6').

PLUGGING

FILE SEC-6-T-25-R124

BOOK PAGE 58 LINE 18

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to

Address. FIRST NATION BANK BLDG. DENVER COLO.

STATE OF Kansas, COUNTY OF Shawnee, SS

FRANK W. GRUBER (employee of owner) or (owner or operator) of the above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank W. Fuller

512 N. Main, Stuffed K.

(Address)

SUBSCRIBED AND SWORN to before me this 14 day of

My commission expires 1-12-1946

Notary Public.

15-185-11735-0000

LOG OF PLAINS EXPLORATION CO. -

MATHER NO. 1 WELL.

c SE NW SW Sec. 6, T.25S, R.12W,
Stafford County, Kansas.

0 - 170	Sand
170 - 515	Red Beds
515 - 730	Red Beds, Shale & Shells
730 - 760	Anhydrite
760 - 1035	Shale & Shells
1035 - 1300	Shale & Lime Shells
1300 - 1570	Shale & Shells
1570 - 1725	Shale & Lime
1725 - 1780	Broken Lime
1780 - 1875	Lime
1875 - 1925	Broken Lime
1925 - 2000	Broken Lime
2000 - 2145	Lime
2145 - 2350	Shale & Lime
2350 - 2560	Shale & Lime Shells
2560 - 2860	Shale
2860 - 2930	Lime
2930 - 3505	Lime
3505 - 3572	Shale
3572 - 3844	Lime (Top of Lansing 3572)
3844 - 3931	Lime & Shale
3931 - 3942	Chat
3942 - 4004	Shale & Lime (Top of Viola 4004)
4004 - 4104	Lime & Chert
4104 - 4185	Shale & Sand (Top of Simpson 4104)
4185 - 4208	Lime (Arbuckle 4185)

Elevation 1923

Dry and abandoned December 11, 1942.

On December 10, 1942 hole was filled with heavy mud to bottom of surface pipe 8 5/8" casing set at 272'. Bridge was set at bottom of surface pipe by means of wooden plug and 15 sacks of cement pumped through drill pipe. Surface pipe was filled with mud and a wooden plug run to 26' and was filled with cement from there to bottom of cellar. Plugging of the surface pipe was done on Dec. 11, 1942; plugging was supervised by A. T. Alexander of the Kansas State Corporation Commission.

