

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-047-21,304-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Sage Drilling Col. Inc. OPERATORS LICENSE NO. 5421

ADDRESS 202 S. St. Francis, Wichita, KS 67202 PHONE # (316) 263-6139

LEASE (FARM) ^S Giles A WELL NO. 2 WELL LOCATION SW NW SE COUNTY Edwards

SEC. 27 TWP. 26 RGE. 16 (~~E~~)~~W~~ (W) TOTAL DEPTH 4660 PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL x D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 500' CEMENTED WITH 375 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD xx POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? operator will be by
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1-28-88 @ 9:20 pm

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

LEONARD WILLIAMSON

PHONE # (316) 793-8366

ADDRESS PO Box 823, Great Bend, KS 67530

PLUGGING CONTRACTOR Duke Drilling Co., Inc.

LICENSE NO. 5929

ADDRESS PO Box 823, Great Bend, KS 67530

PHONE # (316) 793-8366

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED:

Leonard Williamson
(Operator or Agent)

DATE: 1-28-88

RECEIVED
STATE CORPORATION COMMISSION

FEB 02 1988

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S WELL LOG

15-047-21304-0000

DATE COMMENCED: January 22, 1987
 DATE COMPLETED: January 28, 1987

SAGE DRILLING CO., INC.
 Giles A #2
 SW NW SE
 Sec. 27-T26,R16W
 Edwards County, KS

0 - 1085' Surface Soil, Sand, Red Bed, Shale
 1085 - 1099' Anhydrite
 1099 - 3824' Shale, Lime
 3824 - 3829' Shale
 3829 - 3985' Lime, Shale, Lime
 3985 - 4278' Lime
 4278 - 4486' Shale, Sand
 4486 - 4532' Lime, Chert
 4532 - 4608' Sand, Lime
 4608 - 4660' Chert, Lime
 4660' RTD

ELEVATION: 2079 K.B.

Formation Data	
Anhydrite	1085-1099
Heebner	3824
Br. Lime	3970
Kansas City	3985
Base K.C.	4278
Cherokee Sd.	4454
Mississippi	4486
Kinderhook Sd.	4532
Viola	4608
RTD	4660'

Surface Pipe: Set new
 8-5/8", 23# at 500' with
 375 sacks common, 2% gel,
 3% c.c.

A F F I D A V I T


STATE OF KANSAS
 COUNTY OF BARTON) ss.

LEONARD WILLIAMSON of lawful age, does swear and state that the facts
 and statements herein are true and correct to the best of his knowledge.

Leonard Williamson
 Leonard Williamson

SUBSCRIBED AND SWORN to before me this 1st day of February, 1988.

Dorothy M. Hogue
 Notary Public



RECEIVED
 STATE CORPORATION COMMISSION

FEB 04 1988

CONSERVATION DIVISION
 Wichita, Kansas