



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 25, 1995

F G Holl Company L L C
6427 E Kellogg P O Box 780167
Wichita KS 67278-0167

Cudney B 9 20974-00-00
API 15-047-21,974
1875 FNL 990 FEL
Sec. 04-26S-16W
Edwards County

Dear Art Merrick,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - CUDNEY "B" 924
Located: 1875' FNL; 990' FEL, NE/4, Section 4-26S-16W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

RECEIVED
KANSAS CORPORATION COMMISSION

COMMENCED: December 6, 1981
COMPLETED: December 12, 1981

JAN 24 1995

TOTAL DEPTH: 4535'

<u>LOG</u>	<u>CASING RECORD</u>	CONSERVATION DIVISION WICHITA, KS
0 - 260 Sand and Gravel	Ran 9 joints 8 5/8" OD casing. 420.65' pipe set at 433' K.B. Cemented with 375 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 4:00 PM, 12-6-81, by Howco.	
260 - 1081 Shale		
1081 - 1092 Anhydrite		
1092 - 1428 Shale		
1428 - 4535 Lime and Shale	Ran 114 joints 4 1/2" casing. 4520.77' pipe set at 4530' K.B. Cemented with 75 sacks Lite and 75 sacks 50/50 Pozmix, 18% salt, 5# gilsonite, 3/4 of 1% CFR-2, 1/8# fiber, 1/8# flocele. Plug down at 2:45 PM, 12-12-81, by Howco.	

Deviation Surveys: 1 3/4° at 2078'
1 1/2° at 4535'