

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

RECEIVED

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

JAN 23 1995

API # 15-047-20,991-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spot or completion date.

WELL OPERATOR F. G. Holl Company L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)
ADDRESS 6427 E Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE CUDNEY A WELL# 8 SEC. 4 T. 26 R. 16W (East/West)

Irregular Section SPOT LOCATION/QCQQ COUNTY Edwards

1216' FEET (in exact footage) FROM S(N) (circle one) LINE OF SECTION (NOT Lease Line)

1656' ^{NW/4} FEET (in exact footage) FROM E(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE None SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 438' CEMENTED WITH 210 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4565' CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4455 to 4459 Kinderhook Sand

ELEVATION 2088KB T.D. 4575' PBD 4546' ANHYDRITE DEPTH 1084 (+1004)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and Halliburton Plug.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACC-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Merrick PHONE# (316) 995-3171

ADDRESS P.O. Box 158 City/State Belpre, Ks. 67519

PLUGGING CONTRACTOR Pratt Well Service KCC LICENSE # 5893
(company name) (contractor's)

ADDRESS P.O. Box 847 Pratt, Ks. 67124 PHONE # (316) 672-2531

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not Known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/20/95 AUTHORIZED OPERATOR/AGENT: E. Dwight H. Vogel
(signature)



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 25, 1995

F G Holl Company L L C
6427 E Kellogg P O Box 780167
Wichita KS 67278-0167

Cudney A 8
API 15-047-20,991-0000
1216 FNL 1656 FWL
Sec. 04-26S-16W
Edwards County

Dear Art Merrick,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - CUDNEY "A" 8-4
Located: 1216' FNL; 1656' FWL, NW/4, Section 4-26S-16W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 8, 1982
COMPLETED: January 16, 1982

TOTAL DEPTH: 4575'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 437 Gravel and Sand, Shale	Ran 10 joints new 8 5/8" OD casing. 420.90' pipe set at 434' K.B. Cemented with 375 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 11:00 PM, 1-8-82, by Howco.
437 - 745 Sand and Shale	
745 - 1190 Lime and Shale	
1190 - 1204 Anhydrite	
1204 - 3620 Lime and Shale	
3620 - 3835 Lime	
3835 - 4295 Lime and Shale	
4295 - 4425 Lime	
4425 - 4575 Lime and Shale	Ran 117 joints 4 1/2", 10.5# OD casing. 4562.88' set at 4572' K.B. Cemented with 100 sacks 50/50 Pozmix plus regular additives (F. G. Holl mix) and 75 sacks Howco Lite with 18% salt and 3/4 of 1% CFR-2. Plug down at 8:45 AM, 1-16-82, by Howco.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 23 1982

CONSERVATION DIVISION
WICHITA, KS

Deviation Surveys: 1 1/4° at 224'
1/4° at '