

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-075-20284-6000

LEASE NAME HERRMANN

WELL NUMBER 1

3980 Ft. from S Section Line

1300 Ft. from E Section Line

SEC. 1 TWP. 25 SRGE. 39W(E) or (W)

COUNTY HAMILTON

Date Well Completed 06/21/79

Plugging Commenced 08/17/98

Plugging Completed 08/18/98

SEP - 8 1998

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR SHERIDAN ENERGY, INC.

ADDRESS 1000 LOUISIANA, STE. 800, HOUSTON, TX 77002

PHONE # (713) 651-7899 OPERATORS LICENSE NO. WAIVED BY COMMISSION

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 06/02/98 (date)

by STEVE DURANT, DISTRICT I (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? N/A

Producing Formation COUNCIL GROVE Depth to Top 2604' Bottom 2688' T.D. 2727'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chase	Shale & Dolomite	Surface	563	8-5/8"		None
Lower Krider	Dolomite	Surface	2727	5-1/2"		None
Council Grove	Gas Bearing,					
	Siltstone, Conglomerate					
	Sandstone & Limestone					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SEE BACK OF FORM -

10-19-97

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING CO. License No. N/R

Address NESS CITY, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: SHERIDAN ENERGY, INC.

STATE OF TEXAS COUNTY OF HARRIS, ss.


JOHN R. McKNIGHT

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John R. McKnight

(Address) 1000 LOUISIANA, STE. 800
HOUSTON, TX 77002



SUBSCRIBED AND SWORN TO before me this 12 day of October, 1998

Lavonne Cole
Notary Public

My Commission Expires: 8/31/2000


08/17/98

Pumped via 5-1/2" casing, 30 sacks 60/40 poz with 6% gel & 1/4 lbs. Flocele. Displaced with 61 Bbls fresh water. Pressured to 150 lbs. and shut in over night.

08/18/98

Ran wireline & tagged top of cement at 2000'. Started pumps & broke, circulate with 8-5/8" annulus. Pumped 125 sacks 60/40 poz & 100 sacks Class A. Circulate cement via 8-5/8" to pit. Shut down pumps. Hole standing full of cement. Plugging witnessed & approved by Kevin Strube (KCC District I). Cut off & capped casing. Plugging completed 08/18/98.

J. Connor Consulting, Inc.



October 9, 1998

Kansas Corporation Commission
Conservation Division
130 South Market, Rm 2078
Wichita, Kansas 67202-3802

Re: Sheridan Energy, Inc.
Form CP-4, Plugging Report
Herrmann No. 1, API #15,075-20284
NE/4, Sec 1-T25S-R39W
Hamilton County, Texas

Gentlemen:

On behalf of Sheridan Energy, Inc., enclosed is Form CP-4, fully executed and notarized, for the referenced well. This well was acquired by Sheridan in a package of properties purchased from Pioneer Resources in December 1997. Sheridan has no other operations in the state of Kansas and does not have a KCC license number.

In June 1998, Sheridan received a waiver to the license requirement contingent upon immediate plugging of the Herrmann No. 1. Plugging operations were completed in August 1998.

Should you have questions or require additional information, please contact me at (281) 578-3388.

Sincerely,

J. CONNOR CONSULTING, INC.

Wanda E. Richmond
Regulatory Consultant

/wer
Enclosure

cc: Steve Messer, Sheridan Energy, Inc.
Kansas Corporation Commission, District 1, Dodge City, KS

RECEIVED
KANSAS CORP COM
OCT 19 9 21 16