


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Ford County, Sec. 12 Twp. 25S Rge. (E) 21(W)  
Location as "NE/CNW/SW" or footage from lines C NE SW  
Lease Owner Rains & Williamson Oil Company  
Lease Name Konrade Well No. 1  
Office Address 1425 Wichita Plaza Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-14 19 66  
Application for plugging filed 3-14 19 66  
Application for plugging approved 3-14 19 66  
Plugging commenced 3-14 19 66  
Plugging completed 3-14 19 66  
Reason for abandonment of well or producing formation no oil or gas found  
in commercial quantities.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Ed Eads, Sublette, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4850 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	316.71	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 700', spot 35 sacks cement. Mud back and pushed plug to 350' and spot 35 sacks cement. Mud back to 45', set solid bridge and capped with 15 sacks.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 18 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Company  
Address 1425 Wichita Plaza Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
Wilson Rains  
1425 Wichita Plaza Bldg. Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of March, 19 66

My commission expires PAULINE ARNETT  
My Commission Expires Feb. 26, 1967

Pauline Arnett  
Notary Public.

ROTARY DRILLING LOG

OPERATOR: Rains & Williamson Oil Co.  
 #1 Konrade  
 C NE SW Section 12-25S-21W  
 Ford County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.  
 Commenced: 3-2-66  
 Completed: 3-14-66  
 Remarks: Set 316.71' of 8-5/8" surface pipe with 200 sacks of GL3.

FORMATIONS:

Soil & Clay	40'
Shale	75'
Sand	85'
Shale	140'
Sand	155'
Shale	940'
D. Sand	1045'
Shale & Red Bed	1418'
Anhydrite	1440'
Shale	2260'
Shale & Lime	2385'
Lime w/shale	2510'
Lime	2890'
Lime & Shale	3165'
Shale w/Lime Streaks	3285'
Shale	3435'
Shale & Lime	3565'
Lime & Shale	3653'
Shale & Lime	3920'
Shale w/Lime Streaks	4000'
Shale & Lime	4130'
Lime	4395'
Lime w/Shale	4475'
Lime	4745'
Lime & Chert	4850'

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 18 1966

CONSERVATION DIVISION  
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 17th day of March, 1966.

My Commission Expires \_\_\_\_\_

PAULINE ARNETT

*Pauline Arnett*

Notary Public

My Commission Expires Feb. 26, 1967