


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Edwards County. Sec. 23 Twp. 25S Rge. 16 (E)W (W)  
Location as "NE/CNWSW" or footage from lines. NE - NE - SE  
Lease Owner Quality Supply Company  
Lease Name Kearns Well No. 1  
Office Address 6320 Jacqueline Wichita, Kansas 67208  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed January 12 19 58  
Application for plugging filed August 8 19 68  
Application for plugging approved 19  
Plugging commenced September 7 19 68  
Plugging completed September 10 19 68  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation Depth to top Bottom Total Depth of Well 4485 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4485'	3593'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Run plug to 4000 ft. Mixed and dumped 5 sacks of cement. Set 15 ft. rock bridge at 300 ft. to 285 ft. Mixed and dumped 10 sacks of cement. Came back next day. Bailed hole down. Dumped 20 sacks of cement. Mudded 15 ft. Capped with 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Flowers Well Servicing, Inc.  
Address P. O. Box 122 Peabody, Kansas 66866

STATE OF Kansas COUNTY OF Marion, ss.  
Douglas G. Porter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Peabody, Kansas 66866 (Address)



Sworn to before me this 19th day of September 19 68  
March 10, 1969  
W. E. Avery Notary Public.

D. R. LAUCK OIL COMPANY, INC.

Kearns #1

NE NE SE Sec.23-25S-16W  
Edwards County Kansas

Commenced: December 28, 1957  
Completed: January 12, 1958

Casing Record: 255' 8 5/8" cemented with 200 sacks-2 sax calcium Chloride.  
4485' 5 1/2" cemented with 100 sacks.

Elevation: GR 2058; DR 2060; KB 2062.

Drillers Log

surface clay	40
sand	198
blue shale	255
shale, shells & sand	360
red bed, shells & sand	615
red bed	935
red bed & shells	1043
Anhydrite	1058
shale & shells	1390
shale & lime	1435
shale	1455
shale & shells	1860
shale & lime	2805
shale & lime stringers	2950
shale & lime	3090
lime & shale	3350
lime	3680
lime & shale	3885
lime	4120
lime & shale	4170
lime	4340
chert	4345
shale & chert	4358
sand	4377
shale	4434
shale & chert- Viola	4485 RTD

Tops

	Sample	Welex
Heebner	3713-1651	3712-1650
Toronto	3731-1669	3731-1669
Douglas	3749-1687	3749-1687
Brown Lime	3854-1792	3854-1792
Lansing	3871-1809	3871-1809
Base Kansas City		4144-2082
Conglomerate	4322-2260	4321-2259
Mississippian	4339-2277	4339-2277
Sand	4350-2288	4350-2288
Viola	4435-2373	4435-2373
Rotary Total Depth	4485-2423	4485-2423
DST #1 (Bee)	4308-4345 open 1 hr; weak, increasing to good blow; Recov. 30' mud; IBHP 1350# in 30 min; FBHP 0# FPO-0#;	
DST #2 (Sun)	4350-4370 open 1 hr, fair blow; recov. 120' gas, 60 ft. slightly oil cut mud; IBHP 1480# in 30 min. FBHP 200# in 30 min. and still increasing FPO-0#.	