

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 23 TWP. 25 RGE. 16W E/W
Location as in quarters or footage from lines:

NE NW NW

Locate Well
correctly on above
Section Platt.

Lease Owner D.R. Lauck Oil Company, Inc.
 Lease Name Wiles #3 Well No. _____
 Office Address Box 488 Ellinwood, Kansas 67526
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 7-26-82
 Plugging completed 7-29-82
 Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom T.D. 4410'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	388'	none
				4-1/2"	4405'	3595'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 4800' and ran 5 sacks cement. Shot casing @3821',
3717' and 3619'. Pulled a total of 96 joints of 4-1/2" casing. Plugged well with
10 sacks gel, 5 sacks hulls, 15 sacks gel, 150 sacks cement, 2% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 82



Irene Hoover
Notary Public.

My Commission expires:

D. R. Lauck Oil Company, Inc. - Wiles #3
221 S. Broadway, Suite 400 NE NW NW Sec. 23-25S-16W
Wichita, Kansas 67202 Edwards County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: February 8, 1982
Completed: February 17, 1982

Drillers Log

Sand	180
Shale	391
Shale & Red Bed	700
Red Bed	1055
Anhydrite	1065
Red Bed & Shale	1615
Shale	3495
Shale & Lime	3675
Lime & Shale	3790
Lime	4410 RTD

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1982

CONSERVATION DIVISION
Wichita, Kansas

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812
 Phone Kiowa 316-825-4618

ALLIED CEMENTING CO., INC.

No 29507

Home Office P. O. Box 31

Russell, Kansas 67665

Date	7/29/82	Sec.	23	Twp.	25	Range	16W	Called Out		On Location	10:30 AM	Job Start		Finish		
Lease	WILKS	Well No.	#3	Location				BECPRE 55 2E	County	ADWARD	State	K				

Contractor	KULSO CASING RULING	
Type Job	PLUG TO MAINTAIN	
Hole Size	7 7/8	T.D. 4410'
Csg. Size	8 7/8	Depth 388'
Tbg. Size		Depth
Drill Pipe		Depth
Tool		Depth
Cement Left in Csg.		Shoe Joint
Press Max.	2000	Minimum
Meas Line		Displace
Perf.		

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
Charge To	D R LAUCK OIL CO INC	
Street	BOX 488	
City	ELLINGWOOD	State KS
The above was done to satisfaction and supervision of owner agent or contractor.		
Purchase Order No.		
X	7/29 7/29	
CEMENT		
Amount Ordered	1505x cement 2906x 3/4" 11	

EQUIPMENT		
Pumptrk	No 105	Cementer TERRY Helper PAUL
Pumptrk	No	Cementer Helper
Bulktrk	160	Driver RUSSELL
Bulktrk		Driver

Consisting of	
Common	1505x 5/8"
Poz. Mix	
Gel. 2 1/2%	7/8"
Chloride 4.5%	200'
Quickset	
14005-55x	1400
Sales Tax	

DEPTH of Job		
Reference:	4000' TRUCK	3400.00
	460 m. @ 100 m	
	8 7/8 PLUG	10.00
	Sub Total	
	Tax	
	Total	

Handling	1875x	900
Mileage	46 mi	600
Sub Total		
RECEIVED STATE CORPORATION COMMISSION Total AUG 04 1982		
Floating Equipment		

Remarks: 55x (WILKS)
 255x OIL / RELEASED PLUG
 1505x CEMENT
 4000' @ 50'

CONSERVATION DIVISION
 Wichita, Kansas