


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail of Collier Report to:  
Conservation Division  
State Corporation Commission  
221 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Edwards County, Sec. 22 Twp. 25 Rge. 16 (E) (W)  
Location as "NE/CNW%SW%" or footage from lines C SW SW NW  
Lease Owner Theodore I. Leben  
Lease Name Budde Well No. 1  
Office Address 905 Central Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-29-62 19  
Application for plugging filed 10-29-62 19  
Application for plugging approved 10-29-62 19  
Plugging commenced 10-29-62 19  
Plugging completed 11-7-62 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Stafford, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4503 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	371'	None
				5 1/2"	4502'	3492'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back to 4200' with sand. Dumped 4 sacks of cement. Bailed hole down to 240'. Dumped 16 sacks of cement. Mudded hole to 40'. Dumped 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 13 1962

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Central Pipe Pulling Company  
Address 1416 Coolidge, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Byron Johnson (employee of owner) or (owner or operator) of the above-described well, being first, duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Byron Johnson  
P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 62.

My commission expires April 1, 1963 Ulanda Nichols Notary Public.



DRILLER'S LOG

COMPANY:  
CONTRACTOR:  
FARM:  
LOCATION:

Theodore I. Leben & Joe Cox  
LEBEN DRILLING, INC.  
BUDDE #1  
C SW NW Sec. 22-25S-16W  
EDWARDS COUNTY, KANSAS  
9-15-62  
9-27-62

COMMENCED:  
COMPLETED:

0 150  
150 360  
360 373  
373 1070  
1070 1100  
1100 2040  
2040 2680  
2680 2845  
2845 3430  
3430 4432  
4432 4470  
4470 4503  
4503

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 13 1962  
CONSERVATION DIVISION  
Wichita, Kansas

Sand  
Blue Clay  
Clay  
Redbed  
Anhydrite  
Shale & Shells  
Lime  
Lime & Shale Streaks  
Lime & Shale  
Lime  
Lime & Chert  
Lime  
Rotary Total Depth - Set 5 1/2" Casing

Set 8 5/8" used surface casing. 371' Cemented with 305 sacks of Sunset.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Budde #1, located C SW NW of Section 22, Township 25 South, Range 16 West, Edwards County, Kansas, as reflected by the files of Leben Drilling, Inc.

*Byron Johnson*  
Byron Johnson

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 27th day of September, 1962.

*Ulanda Nichols*  
Ulanda Nichols, Notary Public

My Commission Expires:  
April 1, 1963