

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 28 TWP. 25S RGE. 16W E/W
Location as in quarters or footage from lines:
NW SE SE

Lease Owner Oil Properties Co., Inc.
Lease Name Fouse Well No. #1
Office Address Box 335 Andover, Kansas 67002
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 10-15-81
Plugging completed 10-24-81
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom T.D. 4504'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	411'	none
				4-1/2"	4500'	3640'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 4350' and set 4 sacks cement. Shot pipe @3630' and pulled a total of 97 joints of pipe, plugged well with 15 sacks gel, 5 sacks hulls, 10 sacks gel, 8 5/8" plug, 125 sacks 50/50 pos, 4% gel, 3% cc. Plugging Completed.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling CONSERVATION DIVISION
Wichita Kansas

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1981



My Commission expires:

Irene Hoover
Notary Public.