

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County, Sec. 28 Twp. 25S Rge. (E) 16(W)

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines C. NE SW
 Lease Owner Pickrell Drilling Company
 Lease Name Mayhew Well No. 1
 Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed April 7 19 62
 Application for plugging filed April 7 19 62
 Application for plugging approved April 7 19 62
 Plugging commenced April 7 19 62
 Plugging completed April 7 19 62
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4498 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	288'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 260'. Set Plug.
 Cemented with 25 sacks cement.
 Heavy mud to 35'. Set Plug.
 Cemented with 10 sacks cement
 to bottom of cellar. Plugged
 rat hole with 2 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 21 1962
 CONSERVATION DIVISION
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
 Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebits (Conservation Officer) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits
705 Fourth National Bank Bldg., Wichita 2, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1962

My commission expires September 24, 1962

Maxine Johnson
 Maxine Johnson Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Bldg.
 Wichita 2, Kansas
 LOCATION: Mayhew #1 - C
 Sec. 28-25S-16W
 Edwards County, Kansas

Rotary Drilling Commenced 3-27-62

Rotary Drilling Completed 4-7-62

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: 288' (8 jts.) 8 5/8" casing cemented with 260 sacks cement.
 Circulated. Completed at 6:00 P. M. No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

	<u>Circulated for Samples</u>	
175' Top Soil - Sand	4370'	4420'
360' Shale	4380'	4425'
420' Sand	4390'	4435'
1075' Red Bed	4400'	4445'
1100' Anhydrite	4408'	4460'
1970' Shale & Shells		
2015' Lime & Shale		
2575' Lime	<u>Slope Test</u>	
3404' Shale & Lime	1500'	0°
3540' Shale, Lime & Sand	2500'	0°
3630' Shale & Lime	3500'	0°
3680' Lime	4000'	0°
3900' Shale & Lime	<u>S. L. M.</u>	
4250' Lime	2590'	
4325' Lime & Shale	3680'	
4380' Lime	4408'	
4420' Lime & Chert		
4435' Sand & Chert		
4463' Mississippi		
4485' Chert, Sand & Shale		
4498' Viola R.T.D.		

RECEIVED
 STATE CORPORATION COMMISSION
 APR 24 1962
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS

COUNTY OF SEDGWICK } ss.:

On this 20th day of April, 19 62, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
 Maxine Johnson Notary Public