

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Edwards County, Sec. 28 Twp. 25 Rge. 16 (E) (W)X

Location as "NE/CNW/SW" or footage from lines. C SE SE  
Lease Owner. Leben Oil Co.  
Lease Name English Well No. 2  
Office Address. P. O. Box 486 Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 3-31-71 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 4-21-71 19\_\_\_\_  
Plugging completed 5-6-71 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4494 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	306	None
				5 1/2"	4494	645.31

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed a plug to 4300'. Dumped 35 feet sand and 5 sacks cement. Shot pipe at 3885'. Shot at 3784' and 3690'. Laid down 21 jts. 5 1/2" casing. Squeezed well with 2 sacks hulls, 15 sacks gel and 100 sacks cement.


RECEIVED  
STATE CORPORATION COMMISSION  
JUN 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Co., Inc.  
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well has filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
P. O. Box 221 Great Bend, Kansas 67530  
(Address)



Subscribed and sworn to before me this 22nd day of June, 19 71  
Elaine H. Taylor Notary Public.

My commission expires December 14, 1973

HELMERICH & PAYNE, INC. - Operator

SIFRA PETROLEUM CO., INC. - Contractor

ENGLISH #2  
C SE SE  
Sec. 28-25S-16W  
Edwards County, Kansas

T. D.: 4494'  
Elev.: 2078' F.P.

Commenced: 8-1-62  
Completed: 8-13-62

Casing:

8-5/8" Set at 306' w/  
5-1/2" Set at 4494' w/

Cement:

250 sx. Sunset Cement  
100 sx. Salt Saturated

FORMATION	DEPTH
Sand	210
Shale	306
Shale & Sand	365
Red Bed	870
Red Bed & Sand	1070
Anhydrite	1090
Shale & Shells	1995
Lime	2025
Lime & Shale	2330
Lime	2645
Lime & Shale	3535
Lime	4417
Conglomerate	4425
Lime & Shale - Cherty	4494

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

RECEIVED  
OIL AND GAS COMMISSION

APR 6 1971

CONSERVATION DIVISION  
*C.T. Alexander*  
Drilling Superintendent

Subscribed and sworn to before me this 15th day of August, 1962.

*Jersey Ditz*  
Notary Public

My commission expires: 10-17-63