

API NUMBER 15-047-20,867-0000

LEASE NAME Smith "D"

WELL NUMBER #K 2

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 22 TWP. 25 RGE. 16 (E) or (W)

COUNTY Edwards

Date Well Completed \_\_\_\_\_

Plugging Commenced 10-10-90

Plugging Completed 10-23-90

LEASE OPERATOR Pintail Petroleum LTD  
ADDRESS 412 E. Douglas, Suite One, Wichita, Ks. 67202

PHONE # (316) 687-3450 OPERATORS LICENSE NO. 5086

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 12, 1990 (date)  
by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filled? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4456'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 379'   | None       |
|           |         |      |    | 4-1/2" | 4449'  | 2,384.17'  |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 4250' and 4 sacks cement. Shot casing at 3413', 3017', 2807', 2606' & 2363'. Pulled 46 joints of 4-1/2" casing. Howco plugged well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls and 150 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 500 psi and shutin 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum, LTD.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 25th day of October, 1990

Iona M. Leatherman  
Notary Public

My Commission Expires: \_\_\_\_\_  
Iona M. Leatherman  
Barton County, Kansas  
My Appt. Exp. 9-26-91

