

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas.

AL

WELL PLUGGING RECORD

Edwards County. Sec. 29 Twp. 25 Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner n Rudy Herman Oil Operations

Lease Name Parker #1 Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 10-28-60 19

Plugging completed 11-11-60 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 4477 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	234'	None
				5-1/2"	4472'	2525'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4454' and found it clear.
Ran sand from 4454' to 4340' and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing.
Bailed fluid to 200', set 10' rock bridge to 190' and dumped 20 sacks of cement. Mudded hole to 40' set 10' rock bridge to 30' and ran 10 ~~sacks~~ sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

MAR 6 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November, 1960

My commission expires May 20, 1964

Milton J. Vliet
Notary Public.




WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. HONAKER-DAVIS DRIG. CO., ETAL
Farm- Parker No. 1

SEC. 29 T. 25 R. 16W
C NE NE

Total Depth. 4479'
Comm. 6-24-59 Comp. 7-14-59
Shot or Treated.
Contractor. Honaker -Davis Drig. Co.
Issued. 4-23-60

County Edwards
KANSAS



Elevation. 2078

Production. 10 BOPD

CASING:

8 5/8" 287' cem. w/250 sx.
5 1/2" 4477' cem. w/150 sx.

Figures indicate Bottom of Formations.

sand & gravel	180
blue shale	287
shale	350
red bed & shale	1090
anhydrite	1110
shale & red bed	1740
shale	2170
lime & shale	2716
shale & lime	2870
lime & shale	3580
lime	3645
lime & shale	3985
lime	4110
lime & shale	4156
lime	4210
lime & shale	4470
lime & chert	4479RTD
Total Depth	

TOPS: SCOUT	
Heebner	3746
Toronto	3767
Douglas	3788
Brown Lime	3890
Lansing	3896
Base Kansas City	4178
Base Ft. Scott	4343
Mississippi	4365
Kinderhook Sand	4378
Viola	4473

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1964
CONSERVATION DIVISION
Wichita, Kansas