


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County. Sec. 29 Twp. 25 Rge. 16 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C of NW NE

Lease Owner D. R. Lauck Oil Co.
Lease Name Parker B#1 Well No. _____
Office Address Ellinwood, Kansas 67526
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed 19 _____
Application for plugging filed 19 _____
Application for plugging approved 19 _____
Plugging commenced 12/18/78 19 _____
Plugging completed 12/21/78 19 _____
Reason for abandonment of well or producing formation
depleted _____

If a producing well is abandoned, date of last production
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes _____

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4490
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	349	none
				5 1/2"	4488	36 3565

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 4300' and ran 5 sacks cement. Shot pipe at 3595', 3550', pulled
108 joints. Squeezed hole with 5 sacks hulls, 20 sacks gel, released plug
and displaced with 125 sacks 60/40 pozmix, 2% gel and 3% cc.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1978

CONSERVATION DIVISION
STATE CORPORATION COMMISSION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELS0 CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELS0 (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kels0
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of December, 19 78.

My commission expires _____



Margaret Melcher
Notary Public.

D. R. Lauck Oil Company, Inc. - Parker "B" #1
C NW NE Sec. 29-25S-16W
Edwards County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: July 28, 1978
Completed: August 7, 1978

Drillers Log

Clay	35
Sand	158
Shale	300
Sand	313
Shale	352
Shale & Lime	3365
Lime & Shale	3840
Lime	4490 RTD

RECEIVED
STATE CORPORATION COMMISSION

NOV - 3 1978

CONSERVATION DIVISION
Wichita, Kansas