


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Edwards County, Sec. 10 Twp. 25 Rge. 16 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NW  
Lease Owner Harms-Burt Drilling Company  
Lease Name Breitenbach Well No. 1  
Office Address Box 184, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 6 1956  
Application for plugging filed " 6 1956  
Application for plugging approved " 6(verbally) 1956  
Plugging commenced " 6 1956  
Plugging completed " 6 1956  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A.Rives, Box 8, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4690 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface		0	225'	8 5/8"	225'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud from total depth to 220' with plug set at this point and 20 sacks of cement on plug. Filled with heavy mud to 30' with plug and 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Company  
Address Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms  
Box 184, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12 day of October, 1956

My commission expires 1-20-58

Mary E Van Pelt  
Notary Public.  
STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC 10 T 25 R 16w  
BOOK PAGE 105 LINE 21

OCT 13 1956  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

Company: Harms-Burt Drilling Co.

NE NE <sup>NW</sup> Section 10-25S-16W

Farm: Breitenbach #1

Edwards County, Kansas

Commenced: September 17, 1956

Completed: October 6, 1956

Elevation: 2075 KB

0 - 175	sand	3830 - 4075	lime
175 - 225	shale & shells	4075 - 4176	lime & shale
225 - 450	shale	4176 - 4214	lime
450 - 565	shale red bed	4214 - 4265	lime & shale
565 - 675	sand	4265 - 4273	sand
675 - 1030	shale & shells	4273 - 4279	chat
1030 - 1058	anhydrite	4279 - 4310	chert-lime
1058 - 1940	shale & shells	4310 - 4330	lime
1940 - 2085	lime - shale	4330 - 4353	lime & chert
2085 - 2385	lime	4353 - 4360	sand-shale
2385 - 2409	shale	4360 - 4410	shale
2409 - 2730	lime & shale	4410 - 4543	lime & chert
2730 - 2880	shale & lime	4543 - 4578	lime
2880 - 3010	lime & shale	4578 - 4588	shale & lime
3010 - 3118	shale-lime	4588 - 4658	lime & shale
3118 - 3825	lime & shale	4658 - 4690	lime
3825 - 3830	Brown Lime	4690	T.D.

Set 225' of 8 5/8" surface pipe. Cemented with 200 sacks of common cement and 3 sacks of calcium chloride.

Tops: Anhydrite 1030  
 Brown Lime 3825  
 Lansing-K.C. 3830  
 Mississippi 4273  
 Arbuckle 4658

Drill Stem Test: #1 3836 - 3872 Open 1 hour. Shut in 20 min. Recovered 170' slightly oil & gas cut mud. 50' oil & gas cut water.  
 Drill Stem Test: #2 4261 - 4279 Open 1 hour. Shut in 20 min. Recovered 3450' gas. 25' mud. BHP-705#  
 Drill Stem Test: #3 4320 - 4360 Open 1 hour. Shut in 20 min. Recovered 35' mud.

Ran electric log.

Dry, plugged and abandoned.

AFFIDAVIT

State of Kansas )  
 )SS  
 County of Barton)

I, Allan Harms of Harms-Burt Drilling Company, being first duly sworn on oath state: I have knowledge of the facts, statements, and matters herein contained and the same are true and correct.

Signed Allan Harms

Subscribed and sworn to before me this

12 day of October 1956

Mary E Van Pelt  
 Notary Public

My commission expires 1-20-58

PLUGGING  
 FILE SEC 10 T 25 R 16W  
 BOOK PAGE 105 LINE 21

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 15 1956  
 CONSERVATION DIVISION  
 WASHINGTON, KANSAS