

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Edwards County. Sec. 9 Twp. 25 Rge. (E) 6 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NWC NW/4
Lease Owner. B & R Drilling, Inc.
Lease Name. Massey Well No. 1
Office Address. B & R Drilling, Inc.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. 3/19 19. 49
Application for plugging filed. 5/18 Verbally 19. 49
Application for plugging approved. 5/18 Verbally 19. 49
Plugging commenced. 5/18 19. 49
Plugging completed. 5/24 19. 49
Reason for abandonment of well or producing formation. Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production. 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. C. D. Stough
Producing formation. Depth to top. Bottom. Total Depth of Well. 3995 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	502'	None
				5 1/2	3809'	2340'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

Plugged back with crushed rock from 3501' to 3480'. Ran 5 sax cement at 3480' with dump bailer; filled hole with mud to 250'. Dumped 15 sax cement at 250', filled with mud to 30', dumped 10 sax cement for cap.

RECEIVED
Conservation Division
MAY 31 1949
STATE CORPORATION COMMISSION
KANSAS


(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to. B & R Drilling, Inc.
Address. Russell, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Don Roberts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of May, 19 49
[Signature] Notary Public.

My commission expires 6/17/50



B & R Drilling, Inc.
Massey #1

Sec. 9 Twp 25 Rge. 6W
Edwards County, Kansas

Total Depth: 3841
Comm: 1/26/49
Comp: 3/18/49

Top Topeka - 3249
Top K.C. - 3774
Good show gas - 3782-88

Casing
8 5/8 Set @ 502
5 1/2 Set @ 3809

Cement
225 Sacks
110 Sacks

Formation:

Depth:

Sand	150
Sand & Shale	180
Shale & Shells	390
Sand	410
Shale & Shells	502
Red Rock	650
Red Bed & Shells	857
Red Rock & Sand	985
Red Bed	1018
Anhydrite	1040
Shale & Shells	1175
Anhydrite	1190
Lime	1255
Shale & Lime Shells	1410
Shale & Shells	1550
Salt & Shale	1625
Shale	1885
Anhydrite & Shale	2000
Lime & Shale	2045
Lime	2295
Sandy Lime & Shale	2340
Sandy Lime	2390
Lime	2475
Broken Lime	2550
Lime & Shale	2630
Lime	2775
Lime & Shale	2850
Lime	2880
Shale & Lime	3080
Lime	3135
Broken Lime & Shale	3210
Lime & Shale	3535
Lime	3841

STATE OF KANSAS)
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to
the best of my knowledge.

Received
RECEIVED
Nuclear Regulation Div.

Subscribed and sworn to before me this 28th day of March, 1949

Clara L. ...
STATE CORPORATION
REGISTRATION
Notary Public KANSAS

My Commission Expires 6/17/50

PLUGGING
SEC 9 T 25 R 16 W
EDWARDS COUNTY KANSAS
MAY 28 1949