

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 6 Twp. 25 Rge. 16 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NE NE

Lease Owner Mustang Drilling & Exploration, Inc.
Lease Name Gales Well No. 1
Office Address Box 1425, Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole


Date Well completed Dec. 5, 1980
Application for plugging filed Dec. 5, 1980
Application for plugging approved Dec. 5, 1980
Plugging commenced Dec. 5, 1980
Plugging completed Dec. 5, 1980

Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19.

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4550
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	400'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Plug @ 480' w/50 sacks, 400' w/30 sacks 40' w/bridge plug & 10 sacks
10 sacks in rat hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mustang Drilling & Exploration, Inc.

STATE OF KANSAS COUNTY OF BARTON
Milford Martin (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God

(Signature) *Milford Martin*

Box 1425, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 19 8-0

My commission expires



Beverly Shewbart
Notary Public.

DEC 13 1980
12-10-1980
CONSERVATION DIVISION

DRILLERS' WELL LOG

Date Commenced: November 29, 1980
 Date Completed: December 5, 1980

Mustang Drilling & Exploration, Inc.
 "GALES # 1"
 C NE NE
 Sec 6-T25-R16
 Edwards County, Kansas

ELEVATION: 2100 K.B.

0 - 410' Surface Clay, Sand, Sahle
 410 - 1118' Red Bed, Shale
 1118 - 1128' Anhydrite
 1128 - 1470' Shale, Shells
 1470 - 2000' Shale
 2000 - 2365' Shale, Lime
 2365 - 3355' Lime, Shale
 3355 - 3768' Lime
 3768 - 3772' Shale
 3772 - 3796' Lime, Shale
 3796 - 3814' Lime
 3814 - 3912' Shale
 3912 - 3923' Lime, Shale
 3923 - 4198' Lime
 4198 - 4337' Lime, Shale
 4337 - 4393' Snad
 4393 - 4522' Lime, Shale, Sand, Chert
 4522 - 4550' Lime
 4550' RTD

FORMATION TOPS (Log)		
Anhydrite	1118	
Topeka	3355	-1255
Heebner	3768	-1668
Toronto	3796	-1696
Douglas	3814	-1714
Brown Lime	3912	-1812
Lansing	3923	-1823
Kansas City	4052	-1952
Base K.C.	4198	-2098
Cherokee	4337	-2237
Miss.	4393	-2293
Kinderhook Sand	4426	-2326
Conglomerate	4474	-2374
Kinderhook Shale	4504	-2104
Viola	4522	-2422
Log T.D.	4546	-2446
RTD	4550	-2450

SURFACE PIPE:
 Set used 8 5/8", 24# pipe at 400'
 w/350 sacks Common, 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

I, Milford Martin, of Mustang Drilling & Exploration, Inc. do state that the above is true and correct to the best of my knowledge.

Milford Martin

 Milford Martin

Subscribed and sworn to before me this 8th day of December, 1980.

Beverly Shewbart

 Notary Public

My Appointment Expires:

BEVERLY SHEWBART
 Notary Public
 Barton County, Kansas
 My App't. Exp. April 14, 1982

DEC 10 1980
 CONSERVATION DIVISION
 Wichita, Kansas