

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20752-0000

LEASE NAME Norris

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

2310 Ft. from S Section Line

1320 Ft. from E Section Line

LEASE OPERATOR Oil Producers Inc. of Kansas

SEC. 21 TWP. 25 RGE. 16 (E) or (W)

ADDRESS Box 8647, Wichita, Ks. 67208

COUNTY Edwards

PHONE# (316-672-3440) OPERATORS LICENSE NO. 8061

Date Well Completed _____

Character of Well oil

Plugging Commenced 12-22-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-26-88

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4451'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	384'	None
				4-1/2"	4450'	2,884.70'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 4310' and 4 sacks cement. Shot casing at 3800', 3500'; and 2850'. Pulled 74 joints of 4-1/2" casing. Halliburton squeezed well with 250 # hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 150# hulls, and 125 sacks 60/40 pozmix cement with 6% added gel. Maximum pressure was 500 psi and shut in 300 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. _____

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 88

Iona M. Leatherman
Notary Public

My Commission Expires:

