

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,202-0000

LEASE NAME STAPLETON

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

 C SW NW
SEC. 20 TWP. 25S RGE. 16 ~~NE~~ (W)

COUNTY EDWARDS

LEASE OPERATOR WHITE & ELLIS DRILLING, INC.

ADDRESS P O BOX 48848 WICHITA, KS. 67201-8848

PHONE# (316) 263-1102 OPERATORS LICENSE NO. 5420

Date Well Completed

Character of Well OIL

Plugging Commenced 9-30-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-1-91

The plugging proposal was approved on SEPTEMBER 17, 1991 (date)

by (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4480

PBTD: 4390'

Show depth and thickness of all water, oil and gas formations. . .

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
		0	324	8 5/8	324	0
		0	4479	4 1/2	4479	2085' - 66 TTS.

OCT 14 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

DUMPED 135 GALLONS OF SAND, TOP OF SAND AT 4235', DUMPED 4 SX CEMENT, SHOT OFF CASING AT 2085'.
10-2-91: TOP HOLE PLUG: 300# HULLS, 10 SX GEL, 50 SX CEMENT, 100# HULLS, PLUG, 125 SX
CEMENT, 60-40 POZ, 6% GEL. 50# MAX PRESSURE, VACUUM ON SHUT IN. CEMENT 90' FROM SURFACE,
ADDED 1.1 YARDS OF CEMENT ON 10-4-91

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KANSAS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WHITE & ELLIS DRILLING, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY


PLUGGING CONTRACTOR.

(Employee of ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) 40 PWS, Inc.



SUBSCRIBED AND SWORN TO before me this 9th day of October, 19 91

My Commission Expires: Feb 6, 1993

Dorothy M. Furgason
Notary Public