

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,047-20,237-0800

LEASE NAME Stapleton

WELL NUMBER #2

3960 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 20 TWP. 25 RGE. 16 (E) or (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 10-7-88

Plugging Completed 11-23-88

LEASE OPERATOR White & Ellis Drlg, Inc.

ADDRESS 401 E. Douglas, Suite 500, Wichita, Ks. 67202

PHONE # 316-549-6508 OPERATORS LICENSE NO. 5420

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 21, 1988 (date)

by Richard Lacey and Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	332'	None
				4-1/2"	4449'	2,872.35'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Howco pumped 10 BW, 100# hulls, 25 sacks standard cement blended with 100# hulls down 4-1/2" casing. Displaced plug to 3400'. Shot casing at 3400' and 2850'. Pulled 92 lbs. of 4-1/2" casing. Allied plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 120 sacks 60/40.

(If additional description is necessary, use BACK of this form.) OVER

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White & Ellis Drlg, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 1988

Iona M. Leatherman

My Commission Expires:

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-91

Notary Public

pozmix cement with 6% gel. Maximum pressure was 200 psi and shutin zero.