


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ford County, Sec. 12 Twp. 25S Rge. XX 21 (W)
Location as "NE/CNWSW" or footage from lines C NE SE
Lease Owner Pickrell Drilling Company
Lease Name Field "B" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 26 19 70
Application for plugging filed November 26 19 70
Application for plugging approved November 26 19 70
Plugging commenced November 26 19 70
Plugging completed November 26 19 70
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eyes
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4755 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	313'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 300' w/30 sacks cement, Plug @ 40' w/12 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 - 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature]
C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of November, 19 70

My commission expires _____

January 19, 1973

Esther Lamone
Esther Lamone
Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 11/14/70

Rotary Drilling Completed 11/26/70

LOCATION: Field "B" No. 1, C NE SE Section 12-25S-21W
Ford, County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 15 Jts. 8-5/8" surface casing set @ 313' KB. Cemented with 185 sacks cement. Completed 9:00 P.M. Circulated.

No oil string run. D & A, Plugged 9:30 A.M. November 26, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Surface Soil Clay	
314	Shale, Red Shale - Sand	<u>C.F.S.</u>
520	Blue Shale	4130
560	Sand & Shale	4160
710	Sand - Shale	4168
935	Red Beds	4275
1050	Sand	4515
1411	Red Beds - Shale	4535
1438	Anhydrite	4637
2050	Shale	4680
2295	Shale & Lime Streaks	4735
2935	Lime	4755
3230	Lime - Shale	
3650	Shale & Lime	
3745	Lime - Shale	<u>S.L.M.</u>
3870	Shale & Lime	Strap 4323.79
4030	Lime - Shale	Board 4323.16
4723	Lime	.63 Difference
4740	Lime Chert	
4755	Cherty Lime, RTD	
		<u>Slope Test</u>
		2000
		2500
		3000
		3500
		4000
		4500

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 - 1970
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 30th day of November, 19 70, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamone
Esther Lamone Notary Public