

1041325

TO: STATE CORPORATION COMMISSION

10-28

API NUMBER 15-047-20,457-0000
SE NW SW SEC. 9, T 26 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DESEMO WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY EDWARDS

OPERATOR LICENSE # 5047

WELL TOTAL DEPTH 4730 153.73 FEET

OPERATOR: RUPE OIL COMPANY, INC PRODUCTION CSG: SIZE 4 1/2" @ 4746' WITH 150 SX

NAME AND PO BOX 783010 SURFACE CASING: SIZE 8 5/8" @ 361' WITH 300 SX

ADDRESS WICHITA, KS 67278

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 28 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MANNY BOATWRIGHT

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4673'-75' & 4660'-65'

1ST PLUG SAND TO 4600' WITH 4 SX CEMENT. 2ND PLUG AT 1190' WITH 50 SX CEMENT.

3RD PLUG AT 390' WITH 50 SX CEMENT, 4TH PLUG AT 0-40' WITH 10 SX CEMENT 15 SX GEL.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 28 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BACK TO 4600' WITH 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 2ND PLUG AT 1200' WITH 50 SX CEMENT.

3RD PLUG AT 390' WITH 50 SX CEMENT. 4TH PLUG A 40' WITH 10 SX CEMENT.

11-06-98

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2414' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3

60 286