

To: 1 031204  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

7-22 15-047-21039-0000 38 R

API NUMBER 15-Drilled 6/1/82  
NE NE SW, SEC. 11, T 26 S, R 18 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893

2310 feet from S section line  
2970 feet from E section line

Operator: Texas TEA Oil & Gas Services (bankrupt) /  
Name & Address Pratt Well Service, Inc.  
P.O. Box 847  
Pratt, KS 67124-0847

Lease Name Fletcher/Britton Well # 1  
County Edwards 128.37  
Well Total Depth 3950 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 11 a.m. Day: 22 Month: 7 Year: 19 92

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-5901

were: 4 1/2" at 4800', No perf info available, perforated Lansing-KC, Cherokee Sand, Anhydrite 1200'

1st plug set CIBP at 3950' with 2 sx cement on top,

2nd plug spot 50 sx cement at 1200',

3rd plug spot 50' sx cement at 330',

4th plug spot 25 sx cement at 40'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 22 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3950' with 2 sx cement on top,

2nd plug spotted 50 sx cement at 1200',

3rd plug spotted 50 sx cement at 330',

4th plug spotted 25 sx cement at 40'.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2312' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.) JUL 29 1992

INVOICED (To be observed this plugging.)

DATE 8-11-92

Signed Steve Durrant (TECHNICIAN) CONSERVATION DIVISION Wichita, Kansas

INV. NO. 35928