

1 051729

10-22

15-047-30110-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 7/20/65
C NE SE, SEC. 12, T 26 S, R 18 W/2
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name:
Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Madden Well # 1
County Edwards
Well Total Depth 4597 149.40 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 294

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number
Address P.O. Box 31, Russell, KS 67665-0031

Company to plug at: Hour: 9:30 a.m. Day: 22 Month: 10 Year: 19 93

Plugging proposal received from Ed Mondero
(company name) Pickrell Drilling Company, Inc. (phone) 913-798-2430

Work: 5 1/2" at 4596' w/125 sx cement, Perfs at 4507-31', packer & 30' of tubing at 4530'
1st plug cut tubing off on top of packer and spot 35 sx cement,
2nd plug gel spacer 1000' to surface with cement,
3rd plug pump 100' sx cement down backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 2:50 p.m. Day: 22 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 100 lbs. hulls and 23 sx gel at 4450' followed by
35 sx cement,
2nd plug pulled tubing to 1020' and pumped cement to surface,
3rd plug pumped 140 sx cement down 8 5/8" x 5 1/2" annulus.
Maximum pressure 200 psi and shut in 0 psi.

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
If additional description is necessary, use BACK of this form.

INVOICED
DATE NOV 05 1993
INV. NO. 29145

Signed Richard W. Lacy (TECHNICIAN)