

040374

12-6

15-047-10008-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill completion date 9/9/63  
C NW NE, SEC. 19, T. 26 S, R. 18 W/E  
4620 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5061  
Operator: Robert F. White  
Name & Address: 2400 North Woodlawn, Suite 114  
Wichita, KS 67220

Lease Name Belcher Unit Well # 1  
County Edwards 153.50  
Well Total Depth 4723 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 6 Month: 12 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4723' CIBP at 3400' Perfs at 3336-3341' Elevation 2197' DF

1st plug sand back to 3290' and dump 5 sx cement on top of sand bridge with bailer,

2nd plug pump 50 sx cement at 1000, 3rd plug pump 50 sx cement at 570',

4th plug pump 40 sx cement at 200',

5th plug pump 10 sx cement at 40-0'

Plugging Proposal Received by Mike Spain  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a. Day: 6 Month: 12 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 3290' and dumped 5 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 350 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1241' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.  
DEC 14 1989

Signed Stephen J. Pfeifer  
(TECHNICIAN)

DATE \_\_\_\_\_

INV. NO. 26817