

1080406

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,202-0000

SE SE NE , SEC. 8 , T 25 S, R 16 W/E

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name English Well # 1

Operator: Oil Producers Inc. of Kansas

County Edwards 142.03

Name & Address P. O. Box 8467, North Woodlawn

Well Total Depth 4370 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 386

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:20 am Day: 1 Month: August Year: 1985

Plugging proposal received from Mike Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4369' Perfs at 3930-38'

1st plug sand back to 3880' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

orders by Steve Durrant

Plugging Proposal Received by J. N. Mel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:10 am Day: 1 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 3880' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in 0

Remarks: Recovered 2600' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-14-85

STATE CORPORATION COMMISSION RECEIVED

Signed J. N. Mel (TECHNICIAN)

INV. NO. 9588

AUG 13 1985