

To: 1 121052 7-18
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,068-0000
NE SE SE, SEC. 8, T 25 S, R 16 W/EX
990 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers, Inc. of Kansas
Name:
Address P.O. Box 8647
Wichita, KS 67208

Lease Name Zuercher Well # 1
County Edwards 14.21
Well Total Depth 4345' feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 3:10 p.m. Day: 18 Month: 7 Year: 19 95

Plugging proposal received from Kevin Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

vars: 5 1/2" at 4337' w/150 sx cement, PBSD 4305'; Perfs at 4286-94'

1st plug sand back to 4235' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 18 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4235' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement

Pumping pressure 0-400 psi and shut in 100 psi.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 27 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 7-28-95

INV. NO. 43188

Signed Duane Rankin (TECHNICIAN)