

1 030978

9-2

API NUMBER 15- 047-21,106-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C W/2 W/2 NW, SEC. 26, T 25 S, R 16 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255  
Operator: McGinness Oil Company  
Name & Address: 1026 Union Center Bldg.  
Wichita, KS 67202

3960 feet from S section line  
4950 feet from E section line  
Lease Name Willie McGee Well # 1  
County Edwards 146.25  
Well Total Depth 4500 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 470

Abandoned Oil Well  Gas Well  Input  SWD Well  O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor: Pratt Well Service License Number 5893  
Address: Box 847, Pratt, KS 67124

RECEIVED  
OCT 2 1988  
CONSERVATION DIVISION  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

Company to plug at: Hour: 11 a.m. Day: 2 Month: 9 Year: 19 88

Plugging proposal received from Ken Gates

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4499' Perfs at 4401-06'

1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 2 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 450 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2000' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(Add, delete, or observe this plugging.)

Signed Steve Durrant  
(TECHNICIAN)

INVOICED

DATE 10-6-88

INV. NO. 22449