

15-047-00372-0000

9-16

86

To: 1 040567
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 8/7/59

C NW NW, SEC. 24, T 25 S, R 16 (W) X

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Curtis Well # 2

Operator: Oil Producers, Inc. of Kansas

County Edwards 143.32

Name & Address P.O. Box 8647

Well Total Depth 4410 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 357

Abandoned Oil Well X Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2:15 p.m. Day: 16 Month: 9 Year: 19 91

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4400' w/125 sx cement, Top perf. 4328-32'

1st plug sand back to 4278' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx

cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 3:15 p.m. Day: 16 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 400 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2754.41' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

RECEIVED

STATE CORPORATION COMMISSION

observe this plugging.

INVOICED

SEP 20 1991

DATE 10-7-91

INV. NO. 2328

CONSERVATION DIVISION
Wichita, Kansas

Signed Stephen J. Puffer (TECHNICIAN)