

4-9

75R

To: 1 031071
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,155-0000
120' W of
C NE SE, SEC. 24, T 25 S, R 16 W/E
1980 feet from S section line
780 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5427
Operator: D.R. Lauck Oil Company, Inc.
Name & Address: 221 South Broadway, Suite 400
Wichita, KS 67202

Lease Name Grizzell A Well # 1
County Edwards 143.81
Well Total Depth 4425 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 p.m. Day: 9 Month: 4 Year: 19 90

Plugging proposal received from Jim Meeks

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4425' PBDT 4299' Perfs at 4302-4308, 4289-93'

1st plug sand back to 4240' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12 p.m. Day: 9 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4240' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 100 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix .6% gel by Allied. Recovered 2119' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-24-90

INV. NO. 27949

APR 11 1990
CONSERVATION DIVISION
Wichita, Kansas
04-11-90

Signed Steve Clement (TECHNICIAN)