

To: 1 050666
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20,410-0000
NE SW, SEC. 33, T 25 S, R 21 W/4
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4043

Lease Name Torline Well # 1

Operator: Denver-Alaska Oil Comp.
Name & Address: 350 Indiana St
Suite 410
Golden, Colorado 80401

County Ford 158.44
Well Total Depth 4875 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 367

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co. License Number 5418

Address Box 1389 1105 Walnut Great Bend KS 67530

Company to plug at: Hour: 7:00 pm Day: 8 Month: November Year: 1985

Plugging proposal received from Craig Christopher

(company name) Allen Drilling Co. (phone) 316-793-5581

were: Keep hole full of heavy drilling mud + spot plugs
through drill pipe 1st plug @ 1400' w/50sx of cement
2nd plug @ 660' w/50sx of cement
3rd plug @ 400' w/40sx of cement
4th plug @ 40' w/SBP + 10sx.

Circulate Rathole w/15sx Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:45 pm Day: 8 Month: November Year: 1985

ACTUAL PLUGGING REPORT Kept hole full of heavy drilling mud +

spotted plugs through drill pipe 1st plug @ 1400' w/50sx
2nd plug @ 660' w/50sx
3rd plug @ 400 w/40sx
4th plug @ 40 w/SBP + 10sx

Circulate Rathole w/15sx

Remarks: B.J. Titan pumped 60/40 poz mix 6% gel cement
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-21-85

INV. NO. 11095

RECEIVED
STATE CORPORATION COMMISSION
Signed Richard W. Lacey
(TECHNICIAN)
NOV 14 1985
DEC 13 1985
CONSERVATION DIVISION

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: Approx. October 20, 1985
month day year

API Number 15- 057-20, 410

OPERATOR: License # 4043
Name Denver-Alaska Oil Company
Address 350 Indiana St., Suite 410
City/State/Zip Golden, Colorado 80401
Contact Person John Rakowski
Phone (303) 278-4814

NE/4SW/4. Sec 33 Twp 25 S. Rge 21 East West
(location)
..... 1980 Ft North from Southeast Corner of Section
3300 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License #
Name Allen Drilling
City/State

Nearest lease or unit boundary line 660 feet.
County Ford
Lease Name Torline Well# 1
Domestic well within 330 feet : yes no
Municipal well within one mile : yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water approx. 250 feet
Lowest usable water formation Cheyenne
Depth to Bottom of usable water approx. 600 feet
Surface pipe by Alternate : 1 2
Surface pipe to be set approx. 350 feet
Conductor pipe if any required None feet
Ground surface elevation approx. 2325 feet MSL.
This Authorization Expires 4-18-86
Approved By 10-18-85

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4900 feet
Projected Formation at TD Mississippian
Expected Producing Formations Mississippian

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 10/10/85 Signature of Operator or Agent Ann D. Donnelly Vice President

Form C-1 4/84

Set 350' of 8 5/8 on 10/30/85

PUSHER COAG Cristopher
TD 4875 FORMATION MISS
SURFACE PIPE 8 5/8 @ 367
ANYDRITE _____ ELEVATION _____
STARTING TIME & DATE _____
COMPLETION TIME & DATE 8:45 pm / 8/55
1st PLUG @ 1400 FT. W/ 50 SX
2nd PLUG @ 660 FT. W/ 50 SX
3rd PLUG @ 30' support W/ 40 SX
4th PLUG @ 40 FT. W/ 50 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ _____ SX
WATER WELL PLUGGED W/ _____ SX
CEMENT COMPANY SEM
TECHNICIAN _____

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1985
CONSERVATION DIVISION
Wichita, Kansas