

API NUMBER 15- Completed 3-19-61

To: 1 060779
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NE, SEC. 33, T 25 S, R 21 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7864
Operator: John Indiek
Name & Address: R. R. 1
Offerle, KS 67563

Lease Name Butler Well # 3
County Ford 94.80
Well Total Depth 2917 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor John Indiek License Number 7864
Address R. R. 1, Offerle, KS 67563

Company to plug at: Hour: 9:30 am Day: 30 Month: May Year: 19 85

Plugging proposal received from John Indiek
(company name) John Indiek (phone) 316-659-3470

were: 4 1/2" at 2916' Perfs at 2756-2776'
Pump 100 lbs of Flowseal to bottom

Pump 300 sx cement down 4 1/2" casing
If returns up 8.5/8", close 4 1/2" and pump remainder of cement down 8 5/8"

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 12:45 pm Day: 23 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 5-30-85 - Pumped 220 sx cement down 4 1/2" casing.
Maximum pressure 350 psi and shut in on vacuum

Pumped 80 sx cement down annulus Maximum pressure 550 psi and shut in 550 psi
Ran wire line and cement fell to 620' -- too wet to finish plugging at this time. Will
call back when it dries out.

STATE CORPORATION COMMISSION

1-23-86 - Pumped 2 yards readi-mix with fine sand from 620' to surface. JAN 27 1986

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

DATE FEB 5 1986

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 12342
1-23 MAR 07 1986