

1 070757

11-21

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20,477-0000

N/2 N/2 NE, SEC. 35, T 25 S, R 21 W ~~XX~~

4950 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5015

Lease Name Kate Well # 4

Operator: Hellar Drilling Company, Inc.

County Ford 156.33

Name & Address 125 North Market, Suite 1422

Well Total Depth 4810 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well Gas Well Input Well SWD Well O&A x

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104

Address P.O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 2:30 a.m. Day: 21 Month: 11 Year: 19 89

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Company, Inc. (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1377-98' Elevation 2297'

1st plug at 1420' with 50 sx cement, 2nd plug at 800' with 50 sx cement,

3rd plug at 400' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 4:30 a.m. Day: 21 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1420' with 50 sx cement,

2nd plug at 800' with 50 sx cement,

3rd plug at 400' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

NOV 27 1989

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-89

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 26640

11-21

EFFECTIVE DATE: 11-08-89

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas

NOTICE OF INTENTION TO DRILL 057-20,477

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 15, 1989
month day year

N/2 N/2 NE. Sec 35. Twp 25 S, Rg 21 East West

4950 feet from South line of Section
1320 feet from East line of Section

(Note: Locate well on Section Plat Below)

OPERATOR: License # 5015
Name: Hellar Drilling Company, Inc.
Address: 125 N. Market, Suite 1422
City/State/Zip: Wichita, KS 67202
Contact Person: Don Hellar
Phone: 316 267-2845

County: Ford
Lease Name: Kate Well #: 4
Field Name: COON CREEK NORTH

Is this a Prorated Field? yes X no
Target Formation(s): Mississippian

CONTRACTOR: License #: 5104
Name: Blue Goose Drilling Company, Inc.

Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2297' feet MSL

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 DWO Disposal Wildcat Cable
 Seismic; # of Holes

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 340'

Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 360'

Length of Conductor pipe required: n/r
Projected Total Depth: 4850'

If OWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Formation at Total Depth: Mississippian
Water Source for Drilling Operations: Off-lease irrig. well.

X well farm pond other

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location: _____

DWR Permit #: _____
Will Cores Be Taken?: yes X no
If yes, proposed zones: _____

360' Alt. I Req.

Exp. 5/3/90

AFFIDAVIT

PUSHER Martin Miller
TD 4810 FORMATION MIS
SURFACE PIPE 8 5/8" @ 378'
ANHYDRITE 1377-98' ELEVATION 2297'
STARTING TIME & DATE 230PM 11-21
COMPLETION TIME & DATE 430PM 11-21-89
1st PLUG @ 1420 FT. W/ 50 SX
2nd PLUG @ 800 FT. W/ 50 SX
3rd PLUG @ 400 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ — SX
WATER WELL PLUGGED W/ — SX
CEMENT COMPANY Allied Cemented
TECHNICIAN _____


Spud 11-10-89
360' @ 8 5/8"
Hail wt S.P.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1989

CONSERVATION DIVISION
Wichita, Kansas

Don Goode
plug



Agent: _____

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.