

1060073

4-21

339

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 069-20,242-0000

NW NE SW, SEC. 6, T 25 S, R 28 W/E

2310 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6668

Lease Name Penner Farms Well # 1-6

Operator: Theodore I. Leben

County Gray 162.50

Name & Address 105 S. Broadway, Suite 640

Well Total Depth 5000 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 465

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company License Number 5929

Address 310 W. Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 21 Month: 4 Year: 19 91

Plugging proposal received from Jay Schneider

(company name) Duke Drilling Company (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1878-1935'

1st plug at 1940' with 50 sx cement, 2nd plug at 1070' with 50 sx cement,

3rd plug at 495' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11 a.m. Day: 21 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1940' with 50 sx cement,

2nd plug at 1070' with 50 sx cement,

3rd plug at 495' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1991

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (if not) observe this plugging.

DATE 4-29-91

Signed Case Morris (TECHNICIAN)

INV. NO. 31702

EFFECTIVE DATE: 4-6-91

069-20,242

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date APRIL 08 1991
month day year

NW NE SW Sec 6 Twp 25 S, Rg 28 East West

OPERATOR: License # 6668
Name: THEODORE I. LEBEN
Address: 105 S. BROADWAY, SUITE 640
City/State/Zip: WICHITA, KS 67202
Contact Person: DAVID G. LEBEN/GERALD W. ZORGER
Phone: 316-264-2375

2310 feet from South line of Section
3630 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5929
Name: DUKE DRILLING COMPANY, INC.

County: GRAY
Lease Name: PENNER FARMS Well #: 1-6
Field Name: WILDCAT

Well Drilled for: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OAWO Disposal Wildcat Cable
 Seismic; # of Holes

Is this a Prorated Field? yes no
Target Formation(s): MISSISSIPPIAN
Nearest lease or unit boundary: 330
Ground Surface Elevation: 2756GL feet MSL

If OAWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water: 285
Depth to bottom of usable water: 150
Surface-Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 425
Length of Conductor pipe required: NONE

Directional, Deviated or Horizontal well bore? yes no
If yes, total depth location: _____

Projected Total Depth: 4950
Formation at Total Depth: MISSISSIPPIAN
Water Source for Drilling Operations:
 well farm pond other

DWR Permit #: _____
Will Cores Be Taken?: yes no
If yes, proposed zone: _____

Exp. 10/1/91

APR 24 1991 AFFIDAVIT

300' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

RECEIVED
STATE COMMISSION
Wichita, Kansas

Pusher Jay Schneider
SPUD DATE 4-12-91 INIT. _____

LENGTH SURFACE PLANNED 425

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE _____
SURFACE PIPE 8 1/2" CONDUCTOR 46.5
ANHYDRITE T- 1278 B- 1935 ELEVATION _____

TD 5000 FORMATION _____

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N

Arbuckle Plug @ _____ Ft. W/ SX

Hug./Council @ _____ Ft. W/ SX

Anhydrite Base @ 1940 Ft. W/ 50 SX

1/2 Base Anhy. @ 1070 Ft. W/ 50 SX

1/2, 1/2 Plug @ _____ Ft. W/ SX

Bottom Surface @ 495 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL _____ SX (Irr. Well _____ Pond _____)
Hauling _____

TECHNICIAN CM DATE 4-19-91

TYPE OF CEMENT 60/40 Poz 670 1/4 1/2 ft. each

STARTING TIME 9:02 (AM/PM) DATE 4-21-91

COMPLETION TIME 11:02 (AM/PM) DATE 4-21-91

CEMENT COMPANY Allied