

70:   
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20668-00-01  
Spot: NWNWSW Sec/Twnshp/Rge: 7-25S-32W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: JH BURNSIDE B Well Number: UT 2 EX  
County: FINNEY Total Vertical Depth: 5150 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: PO BOX 4358  
HOUSTON, TX 77210

Conductor Pipe: Size feet: 8/67.38  
Surface Casing: Size 8.625 feet: 1935 WITH 920 SX CMT  
Production: Size 5.5 feet: 3069 WITH 335 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/18/2001 11:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT ON BOTTOM. 1ST PLUG AT 1960' WITH 50 SX CMT. 2ND PLUG AT 1030' WITH 40 SX CMT. 3RD PLUG AT 550' WITH 25 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/20/2001 10:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2825'. PERFS AT 2570-2648'. CIBP @ 3027' WITH 2 SX CMT. CIBP @ 2850' WITH 2 SX CMT. INFO. VERIFIED FROM EXXON-MOBIL RECORDS. 12/18/01: PUMPED 400# HULLS WITH 25 SX CMT TO PLUG PERFS. 12/19/01: 1ST PLUG LOAD HOLE WITH MUD. PUMP 50 SX CMT AT 1790'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" CASING TO 1050'. LOAD HOLE WITH MUD. PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH 5 1/2" TO 590'. PUMP 25 SX CMT. GOOD CIRCULATION. 12/20/01: PULL OUT OF HOLE WITH 5 1/2" TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1800' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland PERT II  
(TECHNICIAN)

RECEIVED

DEC 31 2001

KCC WICHITA

INVOICED

DATE 01-02-02

INV. NO. 2002061115

DEC 26 2001

Form CSG

MP