

To: 1 060094
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-24
API NUMBER 15-055-21,019-6006
C NW SE, SEC. 7, T 25 S, R 32 WXB

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003
Operator: McCoy Petroleum Corporation
Name & Address 110 S. Main, Suite 500
Wichita, KS 67202

1980 feet from S section line
1980 feet from E section line
Lease Name Brookover "A" Well # 1-7
County Finney 167.37
Well Total Depth 5150 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1949

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor BEREDCO License Number 5147
Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 24 Month: 8 Year: 19 91

Plugging proposal received from Gary Marshall
(company name) BEREDCO (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1950'
1st plug at 2900' with 100 sx cement, 2nd plug at 1980' with 50 sx cement,
3rd plug at 1200' with 50 sx cement, 4th plug at 600' with 30 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 a.m. Day: 24 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2900' with 100 sx cement,
2nd plug at 1980' with 50 sx cement,
3rd plug at 1200' with 50 sx cement,
4th plug at 600' with 30 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement,

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED (If not) observe this plugging.

DATE 9-27-91
INV. NO. 33232

Signed Case Morris
(TECHNICIAN)

