

1 030634

055

API NUMBER 15- ~~005~~-20,631-0000

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW, SEC. 32, T 25 S, R 34 ^W _E X

3300 feet from S section line

3180 feet from E section line

should be the Lee "D" 1-32 as per Roy Chase

Lease Name Lee Well # 1

County Finney 169.00

Well Total Depth 5200 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 780

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Operator: Champlin Petroleum Company

Name & Address 6441 NW Grand Blvd., Suite 300

Oklahoma City, OK 73116-2290

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 3:00 pm Day: 31 Month: December Year: 19 85

Plugging proposal received from Mort Schulmarker

(company name) H-30 (phone) 316-263-2043

Elevation 2994 KB

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1896-1884'

1st plug at the base of the Hugoton with 50 sx cement

2nd plug at 1890' with 50 sx cement

3rd plug at 810' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with

10 sx cement Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:45 pm Day: 31 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2440' with 50 sx cement, 2nd plug at 1890' with 50 sx

cement, 3rd plug at 823' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell # 03128379
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

STATE COR.

DATE JAN 07 1986

JAN 6 1986

Signed *Steve Durrant*
(TECHNICIAN)

INV. NO. 11868

CALL MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 12 10 85
month day year

API Number 15- 055-20,631

OPERATOR: License # 6417
Name Champlin Petroleum Company
Address 6441 NW Grand Blvd., Suite 300
City/State/Zip Oklahoma City, OK 73116-2290
Contact Person J. L. Ford
Phone 405-840-5521

SE NW Sec 32, Twp 25 S, Rge 34
(location)
3300 Ft North from Southeast Corner of Section
3180 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse slide)

CONTRACTOR: License # N/A
Name H-30 Drilling Co
City/State

Nearest lease or unit boundary line 540 feet.
County Finney
Lease Name Lee Well # 1-32

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator 251 N. Water, Suite 10
Well Name Wichita, Kans.
Comp Date Old Total Depth 67202
Projected Total Depth 5200 feet
Projected Formation at TD Morrow
Expected Producing Formations Morrow, Marmaton!

Depth to Bottom of fresh water 500 feet
Lowest usable water formation Cheyenne
Depth to Bottom of usable water 900 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 500 feet
Conductor pipe if any required
Ground surface elevation 526.86 feet MSL
This Authorization Expires 5-26-86
Approved By 11-26-85

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 11/25/85 Signature of Operator or Agent J. L. Ford Title Regulatory Analyst
Form C-1 4/84

Morse 12-17-85 750' of 8 5/8"

Drill on

STATE CORPORATION COMMISSION

JAN 6 1986

REGISTRATION DIVISION
STATE OF KANSAS