

1080210
TO: STATE CORPORATION COMMISSION

8-18

API NUMBER 15-075-20,289⁴-0000
C NE _____ SEC. 1, T 25 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 1300 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HERRMAN WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY HAMILTON 88.63

OPERATOR LICENSE # N/A

WELL TOTAL DEPTH 2727 FEET

OPERATOR: SHERIDAN ENERGY INC PRODUCTION CSG: SIZE 5 1/2 " FEET 2727

NAME AND 1000 LOUISIANA STE 800 SURFACE CASING: SIZE 8 5/8" FEET 563'

ADDRESS HOUSTON, TX 72002

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER N/A

ADDRESS PO BOX 430, NESS CITY, KS 67560-0420

COMPANY TO PLUG AT: HOUR: 10:45 AM DAY: 17 MONTH: 08 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MAIT DUBOUIS

(COMPANY NAME) ALLIED CEMENTING (PHONE) 785-798-3843

WERE: PERFS AT 2628 TO 2692

PUMP 300# HULLS, 30 SX CEMENT, PERORATED AT 650' CIRCULATE TO SURFACE.

RECEIVED
KANSAS CORP COM
1998 AUG 20 AM 11:47

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 18 MONTH: 08 YEAR: 1998

ACTUAL PLUGGING REPORT _____

ALLIED PUMPED 300# HULLS & 30 SX 60/40 6% WITH 3%CC. DISPLACED WITH 61 BBL NO PRESSURE,

STAYED, WOULDN'T PRESSURE UP. RAN WIRE LINE TAGGED AT 2000', SHUT IN OVER NIGHT.

ON 8-18-98 RAN WIRE LINE TAGGED CEMENT AT 2000'. ALLIED PUMPED 5 BBL PER MINUTE, WELL

CIRCULATING. (CASING LEAK) PUMPED 125 SX 60/40 6% CEMENT FOLLOWED WITH 100 SX COMMON CEMENT.

WELL CIRCULATED TO SURFACE. (CASING LEAK AT APPROX. 1200').

REMARKS: 60/40 POZMIX 6% BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED
(BID) OBSERVE THIS PLUGGING.

SIGNED Kevin D Strube
(TECHNICIAN) FORM CP-2/3

DATE 8-21-98

INV. NO. 31188

8-18