

5-1

To: 1 051167
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 075-20.316-0000
App. SW NE NE, SEC. 12, T 25 S, R 39 W/EX

TECHNICIAN'S PLUGGING REPORT
Operator License # 5855
Operator: Wallace Oil & Gas, Inc.
Name & Address 50 Penn Place, Suite 850
Oklahoma City, OK 73118

4030 feet from S section line
1250 feet from E section line
Lease Name McDonald Well # 1
County Hamilton 91.23
Well Total Depth 2807 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 641

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 1 Month: 5 Year: 19 89

Plugging proposal received from Bob Sargent
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 2804' PBDT 2804' Perfs at 2621-38, 2654-71, 2678-90'

1st plug pump 20 sx common cement and 1 sx hulls to 2700'

2nd plug pump 35 sx cement at 1160',

3rd plug pump 45 sx cement at 680',

4th plug pump 10 sx cement at 40'.

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1989

Plugging Proposal Received by Richard Lacey
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 5:30 p.m. Day: 1 Month: 5 Year: 1989

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement and 1 sx hulls to 2700',

2nd plug pumped 35 sx cement at 1160',

3rd plug pumped 45 sx cement to 680',

4th plug pumped 10 sx cement to 40'.

Remarks: Used common cement by Sargents. Recovered 1320' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

(if desired, you may observe this plugging.)

DATE 5-10-89

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 24746
5-1