

1 040480

10-23

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,867-0000

NE NE SE, SEC. 22, T 25 S, R 16 W/E

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Smith Well # D-2 ?

Operator: Pintail Petroleum Ltd.

County Edwards 144.82

Name & Address 412 E. Douglas, Suite One

Well Total Depth 4456 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 23 Month: 10 Year: 19 90

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4449' w/150 sx cement, Perfs at 4342-50'

1st plug sand back to 4290' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 p.m. Day: 23 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4290' and dumped 4 sx cement on top of sand bridge through bailer.

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 150 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2386' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-6-90

INV. NO. 29844

OCT 30 1990

CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature] (TECHNICIAN)