

1030307

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-20,491-0000

C SE NE, SEC. 29, T 25 S, R 16 W/E  
3300 feet from ~~XXX~~ section line  
660 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Alva Parker Well # 1

Operator: Pintail Petroleum, Ltd.  
Name & Address 405 Century Plaza  
Wichita, KS 67202

County Edwards

Well Total Depth 4419 143.62 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 24 Month: October Year: 19 84

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4414' Perfs at 4261-71'

1st plug pump 2 sx hulls and 35 sx cement and 4 1/2" plug to bottom.

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug, and pump 125 sx cement.

Plugging Proposal Received by Steve Bennett  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 5:45 pm Day: 24 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4414' Perfs at 4261-71'

1st plug pumped 2 sx hulls, and 35 sx cement and 4 1/2" plug to bottom, 2nd plug squeezed

well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8"

rubber plug and pumped 125 sx cement.

STATE CORPORATION COMMISSION

OCT 31 1984

Maximum pressure 200 psi and shut in pressure 100 psi.

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

(XXX / did not) observe this plugging.

Signed Steve Bennett  
(TECHNICIAN)

INVOICED  
DATE 11-7-84  
INV. NO. 4686