

1 120369

1-24 15-047-20020-0000 301 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 11/29/67

C SE, SEC. 10, T 25 S, R 16 W/E
1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5427

Lease Name Julian Well # 1

Operator: D.R. Lauck Oil Company, Inc.
Name & Address: 221 South Broadway, Suite 400
Wichita, KS 67202

County Edwards 145.93

Well Total Depth 4490 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Stepco Well Service License Number

Address P.O. Box 265, Ellinwood, KS 67526

Company to plug at: Hour: 11 a.m. Day: 24 Month: 1 Year: 19 90

Plugging proposal received from Melvin Urban

(company name) D.R. Lauck Oil Company, Inc. (phone) 316-564-2013

were: 5 1/2" at 4470' PBD 4448' Perfs at 4302-34' (2 sets)

1st plug spot 20 sx cement and 1 sx hulls at bottom.

2nd plug pump 25 sx cement at 1100',

3rd plug circulate from 720-0',

4th plug pump 100 sx cement down annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 3:30 p.m. Day: 24 Month: 1 Year: 1990

ACTUAL PLUGGING REPORT 1st plug ran tubing to 4356' and pumped 20 sx cement displaced

with 16 barrels of water, 2nd plug layed down 104 joints of tubing and pumped 25 sx

cement at 1121', 3rd plug layed down 13 joints of tubing and circulated with 65 sx cement,

4th plug layed down all tubing and topped 5 1/2" casing with 5 sx cement,

5th plug pumped in 8 5/8" X 5 1/2" annulus with 100 sx cement.

Shut in pressure 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

JAN 30 1990

CONSERVATION DIVISION Wichita, Kansas

INVOLCED

DATE FEB 07 1990

Signed [Signature] (TECHNICIAN)

INV. NO. 27349

APR 17 1990