

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1975

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D.R. Lauch Oil Co Inc

Complete Address 301 S Broadway Wichita, KS

Lease Name Ansel Well No. 2

Location C SW/NE Sec. 23 Twp. 25 Rge. 16 (E) (W) W

County Edwards Total Depth 4420

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelse Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 11:30 AM Day 12 Month 9 Year 1975

The above well was plugged as follows:

347 ft 8 5/8 surface cement circulated. 4420 ft 5 1/2 long string
cemented with 125 sacks. Top perf. 3337 ft. Sand to 4200 ft, 5 sacks
cement with bailer. Pulled 3440 ft 5 1/2. Pump 3 sacks hulls, 10 sacks
gel, 100 sacks cement to surface.

Pumped by Allied Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9-16-75

INV. NO. 1919-W