

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name H & H Supply Company

Complete Address: Box 95226, Oklahoma City, Oklahoma 73109

Lease Name Troy Mahoney-Butler Well No. 5

Location NE NW Sec. 33 Twp. 25 Rge. 21 ~~(E)~~ (W)

County Ford Total Depth 4835'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Forbes Casing Pulling Co.

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 2:30 Pm Day 28 Month 4 Year 1969

The Above well was plugged as follows:

8 5/8" to 192' circulated w/ cement. 4 1/2" to 4327' cemented.

Top perforations 4229' Plug bottom w/ 20 sacks cement

Top of cement 4000' Mud 4000' to 700'

Spotted 30 sacks cement 700' to 600' Mud 600' to 190'

Spotted 30 sacks cement 190' to 100' Mud 100' to 40'

Bridge & 10 sacks cement 40' to 0'. Company Pump

Pulled 1100' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar E. Eaves
Well Plugging Supervisor

INVOICED

DATE 4/30/69

INV. NO. 9690-W