

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil
Duke Drilling Company
Complete Address: 812 UNION CENTER Wichita,
Box 923 Great Bend, Kansas

Lease Name Butler Well No. # 1

Location C SE ^{NE} Sec. 33 Twp. 25S Rge. 21(E) (W)

County Ford Total Depth 4880'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Great Bend, Kansas License No. 436

Operation Completed: Hour 8 PM Day 21 Month 8 Year 63

The Above well was plugged as follows:

8 5/8"-268' Circulated w/cement. 4 1/2"-4880' Cemented.

Plug back to 4776' Top Perforations 4715'

Plug bottom w/sand 4776' to 4700' 5 Sax. cement 4700' to 4640'

Mud 4640' to 500' 25 Sax. cement 500' to 425'

Mud 425' to 250' 25 Sax. cement 250' to 175'

Mud 175' to 50' Rock bridge 50' to 40'

15 Sax. cement 40' to surface. Cut pipe off 3' below ground level.

Weld plate on surface. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8/26/63

INV. NO. 7646-4