

KANSAS

14
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name AmArex Inc.

Complete Address 2000 Classen Center, Oklahoma City, Oklahoma

Lease Name Butler Well No. 2

Location C NW NE Sec. 33 Twp. 25 Rge. 21 (E) (W)

County Ford Total Depth 4260'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:00PM Day 3 Month 5 Year 1971

The above well was plugged as follows:

8 5/8" to 206' circulated w/ cement. 4 1/2" to 4260' cemented.

Top perforations 4213' Plug bottom w/ 20 sacks cement.

Top of cement 3900' Mud 3900' to 200'

Spotted 35 sacks cement 200' to 100' Mud 100' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2610' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar J. Evers*
Well Plugging Supervisor

INVOICED
DATE 5/13/71
INV. NO. 3679-W