

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
08-27-63  
AUG 27 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mack Oil ~~Duke Drilling Company~~

Complete Address: 812 UNION CENTER WICHITA  
~~Box 823 Great Bend, Kansas~~

Lease Name Torline Well No. # 1

Location C NW SW Sec. 34 Twp. 25S Rge. 21 (E) (W)

County Ford Total Depth 4786'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Knighé Casing Pulling Company

Address: Great Bend, Kansas License No. 436

Operation Completed: Hour 6 PM Day 25 Month 8 Year 63

The Above well was plugged as follows:

8 5/8"-193' Circulated w/cement. 4 1/2"-4785' Cemented.

Plug back to 4777' Top perforations 4708'

Plug bottom w/sand 4777' to 4700' 5 Sax.cement 4700' to 4640'

Mud 4640' to 500' 25 Sax.cement 500' to 425'

Mud 425' to 175' 25 Sax.cement 175' to 100'

Mud 100' to 50' Rock bridge 50' to 40'

15 Sax.cement 40' to surface. Cut surface pipe off 3' below ground level

Weld plate on surface. Pulled 3424' 4 1/2" pipe. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 8/29/63

INV. NO. 9654-u