

Form CP-3
Rev. 6-26-62

[Handwritten mark]
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Martin & Keller

Complete Address: 1035 Kennedy Bldg. Tulsa, Okla.

Lease Name Leidigh Well No. # 1

Location C NE SW Sec. 22 Twp. 25S Rge. 24 (E/W) (W)

County Ford Total Depth 5319'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling Co.

Address: Wichita, Kansas License No.

Operation Completed: Hour 1230AM Day 8 Month 7 Year 65

The Above well was plugged as follows:

8 5/8" - 345' Circulateed w/cement.

Mud 5319' to 700' Spotted 25 Sax.cement 700' to 625'

Mud 625' to 300' Spotted 25 Sax.cement 300' to 225'

Mud 225' to 40' Plug,Hulls,10 Sax.cement 40' to 0

Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 7/12/65
INV. NO. 1451-W

Signed: [Signature]
Well Plugging Supervisor